

Nama : Winda Umi Fatimatus Sa'diyah

NIM : 2141762055

Absen : 19

Packet Tracer - Investigate Disaster Recovery

Objectives

Part 1: Review a Switch Configuration

Part 2: Backup Files to a TFTP Server

Part 3: Replace a Failed Switch

Part 4: Restore Network Operations

Background / Scenario

In this Packet Tracer (PT) activity, you will back up switch configuration files, replace a failed switch with a new switch, and then restore network operations by applying the backed up configuration from the failed switch to the new switch. The backup configuration files are saved to a Trivial File Transfer Protocol (TFTP) server. You are required to restore the saved files from the TFTP server to get the replacement switch online with as little down time as possible.

Note: The activity opens in the **Wiring Closet** for **HQ**. Although you can navigate out of the **Wiring Closet**, all tasks in this activity will occur inside the **Wiring Closet**. Switching to **Logical** mode is disabled.

Instructions

Part 1: Review a Switch Configuration


In this part, you will review and document the current configuration of the MDF-1 switch in the HQ Wiring Closet. This information will be necessary for manually configuring a replacement switch and verifying the new switch is operating as expected.

Step 1: Observe the contents of NVRAM.

- a. Click **MDF-1 > CLI** tab, and then press **Enter**.
- b. Enter the **enable** command, and then enter the **dir nvram** command to observe the contents of NVRAM.

Question:


What is the size of the startup-config file?



Step 2: Document the VLANs and other important configuration information.

- Enter the **show vlan** command.

What VLANs have been configured on MDF-1?



MDF-1

Physical Config CLI Attributes

IOS Command Line Interface

```

1005 trnet-default          active

VLAN Type  SAID      MTU    Parent RingNo BridgeNo Stp   BrdgMode Trans1
Trans2
-----
1    enet  100001    1500   -       -       -       -   -         0      0
10   enet  100010    1500   -       -       -       -   -         0      0
20   enet  100020    1500   -       -       -       -   -         0      0
50   enet  100050    1500   -       -       -       -   -         0      0
75   enet  100075    1500   -       -       -       -   -         0      0
99   enet  100099    1500   -       -       -       -   -         0      0
999  enet  100999    1500   -       -       -       -   -         0      0
1002 fddi  101002    1500   -       -       -       -   -         0      0
1003 tr   101003    1500   -       -       -       -   -         0      0
1004 fdnet 101004    1500   -       -       -       -   -         0      0
1005 trnet 101005    1500   -       -       -       -   -         0      0

VLAN Type  SAID      MTU    Parent RingNo BridgeNo Stp   BrdgMode Trans1
Trans2
-----

Remote SPAN VLANs
-----

Primary Secondary Type          Ports
-----
MDF-1#
  
```



Copy Paste

☐ Top

Type your answers here.

VLANs, 10, 20, 50, 75, 99, and 999

- b. Enter the **show run** command. Review the output to document the following information, which you will need to manually configure on a switch after a disaster.



Record the following settings in the following table:

MDF-1 Settings	Command Output
VLAN 99 IP Address	192.168.99.150
MDF-1 Settings	Command Output
Default Gateway IP Address	192.168.99.1

VLAN Assignment of Interface F0/1	VLAN 75
Native LAN and Trunk Status of G0/1	VLAN 99

Blank Line. No additional information
Blank Line. No additional information

Part 2: Backup Files to a TFTP Server


In this part, you will copy the configuration files for the MDF-1 switch to the TFTP server. You will then verify that the files are listed on the TFTP server.

Step 1: Enable the TFTP service on the FTP server.

- In the **Wiring Closet**, on the right rack, click the **FTP** server > **Desktop** tab > **Command Prompt**.
- Enter the **ipconfig** command.

Question:

What is the IP address for the FTP server?



```

Cisco Packet Tracer SERVER Command Line 1.0
C:\>ipconfig

FastEthernet0 Connection:(default port)


Connection-specific DNS Suffix...:
Link-local IPv6 Address.....: FE80::290:21FF:FE64:E9B9
IPv6 Address.....: ::
IPv4 Address.....: 192.168.75.2
Subnet Mask.....: 255.255.255.0
Default Gateway.....: ::
                        192.168.75.1

C:\>

```

192.168.75.2

- Click the **Services** tab, and then under **SERVICES**, click **TFTP**.
- Enable the TFTP service.




Step 2: Upload the vlan.dat and the startup-config files to the TFTP server.

- Click **MDF-1**, and then **CLI** tab, if necessary. If you were logged out, enter the **enable** command again.
- Enter **copy flash tftp** command and specify **vlan.dat** as the source filename. You documented the IP address in the previous step. Enter **MDF-1_vlan.dat** for the destination filename.

Question:


Record the command below:



- Enter the **copy startup-config tftp** command to copy the configuration to the TFTP server. You documented the IP address in the previous step. Enter **MDF-1_startup-config** as the destination filename.


Question:

Record the command below:



Step 3: Verify that the files are on the TFTP server.

Click **FTP** server. Under **TFTP** in **SERVICES**, verify the two files are listed in the **File** section. If necessary, refresh the File list by clicking another service and then clicking the TFTP service again.



Part 3: Replace a Failed Switch


Assume that the **MDF-1** switch has failed. This could be from a power surge, a corrupted chip, or some other environmental hazard or hardware failure. In this Part, you will install a replacement switch and move the cable connections from the failed switch to the new switch.

Step 1: Add a new switch to the network.

- On the **Table** in the **Wiring Closet**, locate **spare-switch_01**.
- Click and drag it to the rack below **HQ-WLC-1**.

- c. Click **spare-switch_01** > **CLI** tab, and then press **Enter**.
- d. Enter the following commands to deactivate all the interfaces.

```
enable
configure
terminal
interface range f0/1 - 23, g0/1 -
2
shutdown
exit
```



Step 2: Move the cable connections from the MDF-1 switch to new switch.

- a. On the top toolbar, click **Zoom In** several times until you can easily see the cable connections for both **MDF-1** and **spare-switch_01**.


Alternatively, you can right click each switch and choose **Inspect Front**. But you will need to do this each time you move a connection from **MDF-1** to **spare-switch_01**.

- b. Click and drag a cable connection from **MDF-1** to the same port number on **spare-switch_01**. Repeat until all cables are moved from **MDF-1** to **spare-switch_01**.
- c. To verify cables are in the correct ports, right click **spare-switch_01** and choose **Inspect Front**. Zoom in and then float your mouse over each cable, wait for the information popup, and then make sure the cable connections map to this table.

MDF-1 Interface Port	Connected Device
F0/1	FTP Server
F0/2	MAIL Server
F0/3	AAA-RADIUS Server
MDF-1 Interface Port	Connected Device
F0/15	Net-Admin PC
F0/19	FL-1 F0/19
F0/20	FL-1 F0/20
F0/21	FL-2 F0/21
F0/22	FL-2 F0/22
G0/1	HQ Edge Router

Blank Line, No additional information

- d. Right click the **Rack** and choose **Manage All Cables on Rack**.
- e. Uninstall **MDF-1** from the **Rack**. Click and drag it to the **Table**.
- f. On the top toolbar, click **Zoom Reset**.



Part 4: Restore Network Operations

In this Part, you will manually configure the new switch so that it can access the TFTP server. You will then copy the configuration files from the TFTP server to the new switch and verify the switch is operating as expected.

Step 1: Configure spare-switch_01 to access the network.


To access the TFTP server over the network, the spare switch will need network information configured manually. Enter the following configuration into **spare-switch_01** to connect it to the network and prepare it for TFTP server access.

```
vlan 99 name Admin exit interface vlan
99 ip address 192.168.99.150
```

```
255.255.255.0 exit ip default-gateway
192.168.99.1 interface fa0/1
switchport mode access switchport
access vlan 75 no shutdown interface
g0/1 switchport mode trunk switchport
trunk native vlan 99 no shutdown end
```

Step 2: Test connectivity to the TFTP server.

Enter **ping 192.168.75.2** to verify **spare-switch_01** can access the TFTP server.



Step 3: Download the vlan.dat and startup-config files from the TFTP server.

- Enter the **copy tftp flash** command. Specify the IP address of the TFTP server. The source filename is **MDF-1_vlan.dat**. The destination filename MUST be **vlan.dat**. Confirm you want to overwrite the current vlan.dat file.

Question

Record the command below:



Type your answers here.

```
spare-switch_01# copy tftp flash:
Address or name of remote host []? 192.168.75.2
```


```
Source filename []? MDF-1_vlan.dat
Destination filename [MDF-1_vlan.dat]? vlan.dat
%Warning:There is a file already existing with this name
Do you want to overwrite? [confirm]

Accessing tftp://192.168.75.2/MDF-1_vlan.dat...
Loading MDF-1_vlan.dat from 192.168.75.2: !
[OK - 916 bytes]

916 bytes copied in 0.013 secs (70461 bytes/sec) spare-switch_01#
```

- b. Enter the **dir flash** command to verify the **vlan.dat** file is in the directory.

Record the command below:




```
spare-switch_01#dir flash
Directory of flash:/

 1  -rw-     4670455      <no date>  2960-lanbasek9-mz.150-2.SE4.bin
 4  -rw-        1089      <no date>  config.text
 5  -rw-         916      <no date>  vlan.dat

64016384 bytes total (59343924 bytes free)
spare-switch_01#
```

- c. Enter the **copy tftp startup-config** command. Specify the IP address of the TFTP server. The source filename is **MDF-1_startup-config**. The destination filename MUST be **startup-config**.

Record the command below:




```
spare-switch_01#copy tftp startup-config
Address or name of remote host []? 192.168.75.2
Source filename []? MDF-1_startup-config
Destination filename [startup-config]? startup-config

Accessing tftp://192.168.75.2/MDF-1_startup-config...
Loading MDF-1_startup-config from 192.168.75.2: !
[OK - 3012 bytes]

3012 bytes copied in 0.015 secs (200800 bytes/sec)
spare-switch_01#
```

- d. Enter the **dir nvram** command to verify the startup-config file is now in NVRAM.

Record the command below:



```
spare-switch_01#dir nvram
Directory of nvram:/

 238  -rw-          2838          <no date>  startup-config

2838 bytes total (237588 bytes free)
spare-switch_01#
```

Copy Paste

☐ Top

What is the size of the startup-config file?

The startup-config file is 2838 bytes in size.

Is this the same size as the startup-config recorded in Part 1, Step 1?

Yes


Step 4: Reload and verify the new switch now has the correct configuration.


- Enter the **reload** command. The startup-config file will be copied into RAM and become the running configuration.


Important: Answer **no** to the prompt, **System configuration has been modified. Save?**, and then press **Enter** to confirm reload.

Question:

Record the command below:







- b. After the switch reloads, review the configuration.
 - o The hostname is now be **MDF-1**.
 - o Enter the **show vlan** command and verify VLANs you documented in Part 1, Step 2 are listed.

spare-switch_01

Physical Config **CLI** Attributes

IOS Command Line Interface

```
MDF-1>show vlan
```

VLAN	Name	Status	Ports
1	default	active	
10	Accounting	active	
20	Sales	active	
50	Common	active	
75	Servers	active	Fa0/1, Fa0/2
99	Admin	active	Fa0/3, Fa0/15
999	Unused	active	Fa0/4, Fa0/5, Fa0/6, Fa0/7 Fa0/8, Fa0/9, Fa0/10, Fa0/11 Fa0/12, Fa0/13, Fa0/14, Fa0/16 Fa0/17, Fa0/18, Fa0/23, Fa0/24 Gig0/2
1002	fddi-default	active	
1003	token-ring-default	active	
1004	fddinet-default	active	
1005	trnet-default	active	

VLAN	Type	SAID	MTU	Parent	RingNo	BridgeNo	Stp	BrdgMode	Trans1	Trans2
1	enet	100001	1500	-	-	-	-	-	0	0
10	enet	100010	1500	-	-	-	-	-	0	0
20	enet	100020	1500	-	-	-	-	-	0	0
50	enet	100050	1500	-	-	-	-	-	0	0
75	enet	100075	1500	-	-	-	-	-	0	0
99	enet	100099	1500	-	-	-	-	-	0	0
999	enet	100999	1500	-	-	-	-	-	0	0
1002	fddi	101002	1500	-	-	-	-	-	0	0
1003	tr	101003	1500	-	-	-	-	-	0	0
1004	fdnet	101004	1500	-	-	-	ieee	-	0	0
1005	trnet	101005	1500	-	-	-	ibm	-	0	0

VLAN	Type	SAID	MTU	Parent	RingNo	BridgeNo	Stp	BrdgMode	Trans1	Trans2
1	enet	100001	1500	-	-	-	-	-	0	0
10	enet	100010	1500	-	-	-	-	-	0	0
20	enet	100020	1500	-	-	-	-	-	0	0
50	enet	100050	1500	-	-	-	-	-	0	0
75	enet	100075	1500	-	-	-	-	-	0	0
99	enet	100099	1500	-	-	-	-	-	0	0
999	enet	100999	1500	-	-	-	-	-	0	0
1002	fddi	101002	1500	-	-	-	-	-	0	0
1003	tr	101003	1500	-	-	-	-	-	0	0
1004	fdnet	101004	1500	-	-	-	ieee	-	0	0
1005	trnet	101005	1500	-	-	-	ibm	-	0	0

Remote SPAN VLANs

Primary	Secondary	Type	Ports

MDF-1>

Copy Paste

☐ Top

- Enter the **show ip interface brief** command. Verify that your connected physical ports are now all up.

spare-switch_01

Physical Config CLI Attributes

IOS Command Line Interface

```
MDF-1>show ip interface brief
```

Interface	IP-Address	OK?	Method	Status	Protocol
Port-channel1	unassigned	YES	manual	up	up
Port-channel2	unassigned	YES	manual	up	up
FastEthernet0/1	unassigned	YES	manual	up	up
FastEthernet0/2	unassigned	YES	manual	up	up
FastEthernet0/3	unassigned	YES	manual	up	up
FastEthernet0/4	unassigned	YES	manual	administratively down	down
FastEthernet0/5	unassigned	YES	manual	administratively down	down
FastEthernet0/6	unassigned	YES	manual	administratively down	down
FastEthernet0/7	unassigned	YES	manual	administratively down	down
FastEthernet0/8	unassigned	YES	manual	administratively down	down
FastEthernet0/9	unassigned	YES	manual	administratively down	down
FastEthernet0/10	unassigned	YES	manual	administratively down	down
FastEthernet0/11	unassigned	YES	manual	administratively down	down
FastEthernet0/12	unassigned	YES	manual	administratively down	down
FastEthernet0/13	unassigned	YES	manual	administratively down	down
FastEthernet0/14	unassigned	YES	manual	administratively down	down
FastEthernet0/15	unassigned	YES	manual	up	up
FastEthernet0/16	unassigned	YES	manual	administratively down	down
FastEthernet0/17	unassigned	YES	manual	administratively down	down
FastEthernet0/18	unassigned	YES	manual	administratively down	down
FastEthernet0/19	unassigned	YES	manual	up	up
FastEthernet0/20	unassigned	YES	manual	up	up
FastEthernet0/21	unassigned	YES	manual	up	up
FastEthernet0/22	unassigned	YES	manual	up	up
FastEthernet0/23	unassigned	YES	manual	administratively down	down
FastEthernet0/24	unassigned	YES	manual	administratively down	down
GigabitEthernet0/1	unassigned	YES	manual	up	up
GigabitEthernet0/2	unassigned	YES	manual	administratively down	down
Vlan1	unassigned	YES	manual	administratively down	down
Vlan99	192.168.99.150	YES	manual	up	up

MDF-1>

Copy Paste

☐ Top

End of document

Packet Tracer - Investigate Disaster Recovery

